

切盛計画集計表

路線名：谷相線1号箇所

+ 0.00～+74.00 L=74.00m

切盛 1 / 5

作業項目		合計	礫質土	礫質ルース						m 4	平均距離
総掘削量	CA5	L 391.42	L 253.14	L 138.28							
		C 293.57	C 189.86	C 103.71							
		326.18	210.95	115.23							
総掘削土量変化率		L 1.2000123									
		C 0.9000245									
飛散後土量	CA5	326.18	210.95	115.23							
掘削土質率	CA5	1.0000000	0.6467288	0.3532712							
逸散量	CA5	16.31	10.55	5.76							
流用可能土量	CA5	309.87	200.40	109.47							
盛土	BS3	L 7.44									
		C 5.58									
		6.20									
	BU	L 61.54									
		C 46.15									
		51.28									
	BU3	L 44.08									
		C 33.06									
		36.73									
	計	L 113.06									
		C 84.79									
		94.21									
	同測点内流用盛土	L 113.06	L 73.12	L 39.94							
		94.21	60.93	33.28							
捨土場所1	運搬を伴う CA5(ダンプ)										
		L 258.79	L 167.36	L 91.43							
		215.66	139.47	76.19						218610	1013.68
捨土量合計	運搬を伴う CA5(ダンプ)										
		L 258.79	L 167.36	L 91.43							
		215.66	139.47	76.19							
	捨土量合計 CA5										
		L 258.79	L 167.36	L 91.43							
		215.66	139.47	76.19							
掻均量	捨土場所1 有	L 258.79									
		215.66									
	無	L									
	計	L 258.79									
		215.66									
	合計 有	L 258.79									
		215.66									

L：ほぐした土量， C：締固め後の土量

切盛計畫集計表

路線名：谷相線1号箇所

+ 0.00~+74.00 L=74.00m 切盛 2 / 5

作業項目	合計	礫質土	礫質ルース ²⁾					m 4	平均距離
------	----	-----	---------------------	--	--	--	--	-----	------

[illegible][illegible][illegible]

		1167-89									
--	--	---------	--	--	--	--	--	--	--	--	--

[illegible][illegible][illegible][illegible][illegible][illegible][illegible][illegible]

切取数量計算表

工種 : CA5

路線名 : 谷相線1号箇所

切取 3 / 5

測点名 ＜流用区間距離＞	(修正距離) 単距離	土砂断面積 岩断面積	土砂平均断面積 岩平均断面積	土加減 岩加減	土砂立積 岩立積	飛散量 飛散後立積	逸散量 逸散後立積	現場捨土	＜小計＞ 流用可能立積	礫質土	礫質ルース					
+ 0.00		0.00														
+ 7.00	7.00	0.00														
+11.00	4.00	2.50	1.25		5.00	5.00	0.25 4.75		4.75	4.60	0.40					
+20.50 ＜20.50＞	9.50	4.10	3.30	114.00	145.35	145.35	7.27 138.08		＜142.83＞ 138.08	30.52	114.83					
+26.00	5.50	3.70	3.90		21.45	21.45	1.07 20.38		20.38	21.45						
+29.00	3.00	3.90	3.80		11.40	11.40	0.57 10.83		10.83	11.40						
+33.50	4.50	3.40	3.65		16.43	16.43	0.82 15.61		15.61	16.43						
+42.50 ＜22.00＞	9.00	3.90	3.65		32.85	32.85	1.64 31.21		＜78.03＞ 31.21	32.85						
+44.50	2.00	3.90	3.90		7.80	7.80	0.39 7.41		7.41	7.80						
+52.50	8.00	3.40	3.65		29.20	29.20	1.46 27.74		27.74	29.20						
+55.50 ＜13.00＞	3.00	4.80	4.10		12.30	12.30	0.62 11.68		＜46.83＞ 11.68	12.30						
+74.00 ＜18.50＞	18.50	0.00	2.40		44.40	44.40	2.22 42.18		＜42.18＞ 42.18	44.40						
合計	74.00			114.00	326.18	326.18	16.31 309.87		309.87	210.95	115.23					

盛土数量計算表

路線名 : 谷相線1号箇所

盛土 4 / 5

測点名 〈流用区間距離〉	単距離	BS3					BU					BU3				
		修正距離	断面積	平均	加減	立積	修正距離	断面積	平均	加減	立積	修正距離	断面積	平均	加減	立積
+ 0. 00			0. 00					0. 00					0. 00			
+ 7. 00	7. 00		0. 00					0. 00					0. 00			
+11. 00	4. 00		0. 10	0. 05		0. 20		0. 40	0. 20		0. 80		0. 50	0. 25		1. 00
+20. 50 〈20. 50〉	9. 50		0. 10	0. 10		<1. 15> 0. 95		0. 60	0. 50		<5. 55> 4. 75		0. 60	0. 55		<6. 23> 5. 23
+26. 00	5. 50		0. 10	0. 10		0. 55		0. 40	0. 50		2. 75		0. 40	0. 50		2. 75
+29. 00	3. 00		0. 10	0. 10		0. 30		0. 50	0. 45		1. 35		0. 50	0. 45		1. 35
+33. 50	4. 50		0. 10	0. 10		0. 45		0. 70	0. 60		2. 70		0. 50	0. 50		2. 25
+42. 50 〈22. 00〉	9. 00		0. 10	0. 10		<2. 20> 0. 90		1. 10	0. 90		<14. 90> 8. 10		0. 70	0. 60		<11. 75> 5. 40
+44. 50	2. 00		0. 10	0. 10		0. 20		0. 70	0. 90		1. 80		0. 60	0. 65		1. 30
+52. 50	8. 00		0. 10	0. 10		0. 80		1. 10	0. 90		7. 20		0. 70	0. 65		5. 20
+55. 50 〈13. 00〉	3. 00		0. 10	0. 10		<1. 30> 0. 30		1. 40	1. 25		<12. 75> 3. 75		0. 70	0. 70		<8. 60> 2. 10
+74. 00 〈18. 50〉	18. 50		0. 00	0. 05		<0. 93> 0. 93		0. 00	0. 70		<12. 95> 12. 95		0. 00	0. 35		<6. 48> 6. 48
合計	74. 00					5. 58					46. 15					33. 06

盛土流用計画表

路線名 : 谷相線1号箇所

流用 5 / 5

[illegible]

C：締固め後の土量